



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

GST No. 36CNUPB0012J1Z7

Date: 30-05-2024

To

M/s. Sai Priya Constructions Ltd.
Madhapur, Hyderabad, Telangana.

Sub: Quotation for HMDA land development work.

S.NO	ITEM OF WORK	UNIT	RATE (Rs)
1.	<u>Earth work excavation</u> in road in all kinds of soils except in up to 1' to 1-6" feet depth. Formation of the road, spreading of gravel irrespective of thickness cambering and leveling surface watering and 8 to 10 tones road.	1 Sq.Yrd	45.00
2.	<u>Wet mix:</u> The wet mix with 40mm, 20mm, and 6mm dust all mixing thickness 125mm watering and rolling for best consolidation. The W.B.M Road should be perfectly levelling by maintaining required camber and gradients etc., as per the directions of the developers vibration roller.	1 Sq.Yrd	55.00
3.	<u>B.T.Roads(Hot mix):</u> 30mm consolidated thickness double premixed carpet surfacing over existing metal roads surface by 1mm hard granite broken metal chips with 25mm thickness tack coat and by using 6mm HBG metal chips with 6mm thickness seal coat by using 80/100 grade bituminous 19.20kgs or road surface and rolling with PRR of hot mix vibration rollers capacity	1 Sq.Yrd	100.00



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

	complete item of the work as per standard specification as per the directions of the developers.		
4.	<u>Construction of septic-tank</u> as approved in the layout with CRS masonry walls and RCC slab curing etc. complete	1 Sq.Yrd	15.00
5.	<u>Drainage Lines:</u> All the drainage lines should be provided 6" dia 8" and 12" dia SWG ISI mark (IS651-2007) pipes of approved quality with necessary manholes chambers of the distance not more than 801-0" distance. The manholes should be constructed with cement brick with RCC cover by using 6mm dia rods. Providing channels and neat cement punning etc. as per standard specifications. A separate drainage pipelines drawing will be supplied by the developers as per the site conditions and requirement etc.	1 Sq.Yrd	48.00
6.	<u>Water Tank(Overhead Tank):</u> Overhead tank & sump capacity as per Engineer's design based on the number of plots; whose details as follows:- reinforcement steel (Jayaraju or Sarvottam) used footings mat single mat (12 mm dia) Round beam (20 mm) Round beam (16 mm) Double mate(12 mm) wall vertical rods(12 mm) 6" spacing, horizontal bars 10 mm spacing. ring beam 16 mm, rings 12 mm wall double mat vertical 12 mm horizontal 10 mm taper beam 16 mm dia top slab 10 mm dia single mat ci pipe fixing gi pipe railing staircase gi pipe fixing work tank plastering and painting	1 Sq.Yrd	75.00



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

7.	<u>Water Supply Distribution:</u> All that water supplying distribution line laid with HDPE (Aditya Polymers) make first class quality with pressure pipes of 6 Kg/cm ² of dia 4" and 3" and 2" and IW dia depending upon the requirements the water consumption. A separate drawing will be supplied by the developer by showing all the details of the dia of pipes valves and other fittings as required according to the site conditions and requirements.(Every 30 metres curing point) (with every plot connection provided).	1 Sq.Yrd	35.00
8.	<u>Footpaths filling and flooring & Curb Stones (Ready-made curb stone):</u> C.C. Curb stones of size 16" x 4" x 16" long in cms (1:2:4) prop, by using 6mm HGB chips of approved quality and with neat plastering in cm(1:4) prop and providing grooves etc, curing for 21 days for curb stones. The inner side and of the stone should be provided 3" plain and slope 3" out of 6" head supply and apply 2 coats of paints shade and made as approved over base coat of premier coat and yellow and black paints. All the foot paths are filled with hand murram to curbed stones level and take in neat labelling etc.	1 Sq.Yrd	90.00
9.	<u>Plantation and Fixing Trees:</u> Provided garden and one two numbers of healthy avenue plants are planted for each plot. (One tree planted 25' ft minimum). (Bahuneya, Sapthodia, Tobibiya, Bosia, Star Light, Kadamba, Ficus Pand, FoxTail Palm, konakurpus etc.) all trees are 7' to 8' height. 60' Road plantation (on 6' divider	1 Sq.Yrd	20.00
10.	<u>Harvesting pits:</u> Construction of required no. of water harvesting pit as per HMDA norms specification.	1 Sq.Yrd	12.00



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

11.	<u>Electrical underground cable work:</u> The electrical cable lines are provided on all the roads are III phase. - Single Pole structure with 150mm box pole 11m length 200 A AB switch Single Pole GH Fuse set required insulators 1 No., GI Pipe 3nos. GI pipe 25x3 mm GI flat and etc.. - Main PCC Pannel supply of erection testing and commissioning of LT Kiosk with 1 No. 630 A MCCB for Incoming and 13 Nos. of 160 MCCB for outgoing shall be made for 1.6 mm Thick CRCA Sheet Steel free standing out door Type (IP 55) degree of Protection with power coating. - Sub Panel supply of erection testing and commissioning of Feeder pillar box made of 2 mm CRCA Steel of powder coated paint with 1 No. 160 A TP MCCB as incomer and 14 Nos. 63 A TP MCBS as outgoing indication lamps connectors on an angle frame made out of 40 x 40 x 5mm angle and all other accessories as required. - Supply of (6.0 Meter long single arm swaged type street light pole on plots side or road divider double arm 6.0 meter pole) of 2 meters 4" dia at bottom, 1.5 meters 3" dia at middle 1.5 meters 2.5" inches dia at top and 1.2 meters dia for ARM with built-in-control box with 6 A MCB control with 2 coats red oxide paint as a primer with provision for earthing with 250 x 250 mm 10mm thick MS Base Plate mounting. - Supply fixing of street light fitting 50 watts suitable LED light fitting with Lamp. - Supply of providing testing and commissioning earthing electrode 50mm dia G1 pipe with back	1 Sq.Yrd	190.00
-----	---	----------	--------



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

	fill compound including spreading a homogenous mixture of back fitting compound around the pipe etc., completely as per IS3043. g. Supply of laying 25 x 3 meter GI Strip for earthing. h. 3.5 C x 185 Square MM HT Cable Aluminum Armored cable. i. 3.5 C x 240 Square MM LT Cable Aluminum Armored cable transfer to main panel. j. 3.5 C x 95, Square Meter LT Cable Aluminum XLPE Armored cable main panel to sub-panel feeder pillar. k. 3.5 C x 70 Square MM LT Cable Aluminum XLPE Armored cable main panel to sub-panel feeder pillar. l. 4 x 10 Square MM LT Cable Aluminum Armored cable main panel to sub-panel feeder pillar to each plot. m. 3.5 C x 95 Square Meter LT Cable Aluminum XLPE Armored cable termissin. n. 3.5 C x 70 Sq. Meter L.T. Cable Aluminium XLPE Armored cable termissin.		
--	---	--	--

12.	<u>Park Development:</u> Earth cutting: 1'6"x1 '6"x2" Bendadi filling: Levelling up to 2' CRS, Walls : Park Grills and surroundings and One Gate land tree and children playing instruments will be installed. (1. Small slides 2. Merogo round 3. Sea saw 4. Rainbow 5. Double swing).	1 Sq.Yrd	35.00
-----	--	----------	-------



SRI SAI INFRA DEVELOPERS

Contractor in Layout Developers & Civil Contractors

H.No. Villa no.3, Saket Swarna, Saket colony, kapra,
Dammaiguda Road, Hyderabad - 500062.

Ph: 9959763339

13.	Laying of plotting stones: laying of plotting stones as per demarcation, painting, numbering of plots, sign boards showing the road Nos. and fencing around the mortgage plots with PCC poles and arrangement of boards in the mortgage area as per norms of HDMA, including cost and conveyance.	1 Sq.Yrd	15.00
14.	Construction of Arch: at main road entrance as per Engineer design with all materials and labour .	1 Sq.Yrd	15.00
Per Sq.Yrd		TOTAL	750.00
Rupees :(seven hundred fifty only.)			

Note:

- a) As per HMDA specification per Sq.yard Rs. 750/- (Seven hundred and fifty rupees only) for plotted area.
- b) Bill will be provided with GST of 18% extra, if needed.

Terms & Conditions:

The Landlord has to take care of Survey the Land and marketing the plots and roads and water should be provided by the Landlord and temporary electricity for staying labour. Landlord is requested to get the electricity permission, Transformer and pay related DD amount.

As per agreement the work start within 15 days from the date of agreement, the payment should be paid every 15 days from work started. (The advance of 5% mobilization over the complete work value is requested and same will deducted or adjusted in the final bill)

The Developer hereby agrees to pay the amount to the Contractor depending upon the progress of works, within 30 months' work will be completed, if extra work had done separate payment has to be paid.

Thanking you and assuring you of our best services at all times.

Signature of the Contractor
(B.Balram)